

**UNDERGROUND INJECTION CONTROL
PERMIT APPLICATION**

**Ute Tribal # 03-12
2272' FSL & 575' FWL
Sec. 3, T5S-R3W
Duchesne County, Utah
API # 43-013-31706**

July 2015

Prepared for:
Bruce Suchomel
Groundwater Program, Mail Code 8P-W-UIC
U.S. Environmental Protection Agency
1595 Wynkoop St
Denver, CO 80202-1129

Prepared by:
Petroglyph Energy, INC.
960 Broadway Avenue, Suite 500, P.O. Box 70019
Boise, Idaho 83707
(208) 685-7600
FAX (208) 685-7605

UNDERGROUND INJECTION CONTROL
PERMIT APPLICATION

• HEADER ON CBL
UNREADABLE

• SUNDRY REPORTS

• CBLs FOR AOR WELLS

Ute Tribal # 03-12
2272' FSL & 575' FWL
Sec. 3, T5S-R3W
Duchesne County, Utah
API # 43-013-31706

July 2015

Prepared for:
Bruce Suchomel
Groundwater Program, Mail Code 8P-W-UIC
U.S. Environmental Protection Agency
1595 Wynkoop St
Denver, CO 80202-1129

Prepared by:
Petroglyph Energy, INC.
960 Broadway Avenue, Suite 500, P.O. Box 70019
Boise, Idaho 83707
(208) 685-7600
FAX (208) 685-7605

LIST OF ATTACHMENTS

- | | |
|-------------------|---|
| Attachment No. 1 | Area Topography Map |
| Attachment No. 2 | Site Map |
| Attachment No. 3 | Map of the A-Marker surface |
| Attachment No. 4 | Cross-Sections of the injection formation |
| Attachment No. 5 | Water Analysis |
| Attachment No. 6 | Completion data for all wells in the AOR |
| Attachment No. 7 | CBL for the UIC well |
| Attachment No. 8 | Open hole log for the UIC well |
| Attachment No. 9 | List of owners and Affidavit Notification |
| Attachment No. 10 | Well bore diagrams for the UIC well |
| Attachment No. 11 | P&A procedure |
| Attachment No. 12 | MIT procedure |
| Attachment No. 13 | Surety Bond letter |

**SUMMARY DOCUMENT
UIC WELL APPLICATION
Ute Tribal 03-12
API # 43-013-31706**

The following document contains information provided in support of the application for the conversion of the Ute Tribal 03-12 well to an injection well in the Green River formation in the Antelope Creek Field in Duchesne County, Utah.

The Antelope Creek Field falls within the Uintah and Ouray Indian reservations and is within Indian Country; therefore, for facilities located on the reservation, only EPA-issued UIC permits are necessary for compliance with UIC regulations.

The EPA has issued an Area Permit #UT20736-00000 for the Underground Injection Control for the Antelope Creek Field. This area permit allows for additional producing wells to be converted to injection wells for enhanced recovery.

- (1) Petroglyph Energy, Inc. (Petroglyph) is the operator and only working interest owner of wells located in the Antelope creek Field, Duchesne County, Utah. Petroglyph's business address is provided below:

Petroglyph Energy, Inc.
960 Broadway Avenue, Suite 500
P.O. Box 70019
Boise, ID 83707

- (2) Enclosed as Attachment No. 1 is a topographic map of a portion of the Antelope Creek Field, identifying all wells located in this area. The legal location for the Ute Tribal 03-12 is 2272' FSL & 575' FWL NW/SW Sec. 3, T5S-R3W.
- (3) Attachment No. 2 is a map of the well. This map shows a circle with a ¼ mile radius centered on the Ute Tribal 03-12 well. The ¼ mile radius encompasses the area of review, AOR, within which Petroglyph is required to investigate all wells for mechanical integrity. The ¼ mile radius also identifies mineral ownership; all lands within the AOR are leased to Petroglyph by the Ute Tribal as indicated by yellow shading. The AOR has Ute Tribal 03-05 and Ute Tribal 04-09 well(s) located in its ¼ mile radius.

- (4) Petroglyph proposes to utilize the Ute Tribal 03-12 as an injection well for enhanced recovery in the Antelope Creek Field.
- (5) Injection Zone – The injection intervals are between 4170' and 6150' True Vertical Depth and located in the lower portion of the Green River Formation. The injection zone is confined within a 1980' section between the Green River "A" Lime marker bed and the top of the Basal Carbonate in the lower part of the formation. The injection zone is composed of lenticular calcareous sandstones interbedded with low permeable carbonates and calcareous shales. The lenticular sandstones vary in thickness from 1 to 30 feet.

Confining Zone – The overall confining strata above the injection zone consists of impermeable Green River calcareous shales and continuous beds of microcrystalline dolostone. The confining zone in the Ute Tribal 03-12 is 243 feet thick.

Attachment No. 3 is a structure map of the A-Marker surface.

Attachment No. 4 is a cross-section of the injection interval and confining zone.

- (6) Enclosed as Attachment No. 5 are standard analyses of produced water from three batteries that currently serve as central handling facilities for all project producing wells. The analysis of the Green River formation water from the Ute Tribal 18-08 Satellite Battery is 12805 mg/L of total dissolved solids (TDS), Ute Tribal 21-11 Satellite Battery is 15659 mg/L TDS, and Ute Tribal 34-12-D3 Satellite Battery is 14590 mg/L TDS.

Injectate in the field is a mixture of produced water and fresh make-up water. The nearest injection well is the Ute Tribal 03-14, the most recent analysis of the water being injected into the Green River formation at this location is 6393 mg/L TDS. This analysis is also included in Attachment No. 5.

- (7) A summary of completion data from the Ute Tribal 03-12 and offset wells in the AOR are included in Attachment No. 6
- (8) The cement bond log is included in Attachment No. 7.
- (9) The open hole log for the Ute Tribal 03-12 is included in Attachment No. 8.

(10) The Antelope Creek Field is operated under a Cooperative Plan of Development between the Ute Tribe and Petroglyph Energy. At the Ute Tribal 03-12 location, all mineral owners, surface owners and operators located within the AOR ¼ mile radius have been notified of the submitted EPA application to convert to injection. Attachment No. 9 is the Affidavit of Notification to all owners.

(11) Petroglyph requests a maximum surface injection pressure of **1900psi**. The EPA Area Permit No. UT20736-00000 uses the formula:

$$P_m = (0.88\text{psi/ft} - 0.43\text{psi/ft}(S_g)) D$$

Where:

P_m = Maximum surface injection pressure

0.88psi/ft = Fracture gradient

D = Top perforation depth

0.43psi/ft = Hydrostatic pressure/hydraulic head

S_g = Specific gravity of injection fluid

For the Ute Tribal 03-12:

$$\mathbf{1942\text{psi} = (0.88\text{psi/ft} - 0.43(1.00)) 4316\text{ft}}$$

EPA Area Permit No. 20736-00000 further caps maximum surface pressure at 1900psi.

(12) Three wellbore diagrams for the Ute Tribal 03-12 are in Attachment No. 10. One diagram is for production, one for injection, and one for Plug & Abandonment (P&A).

(13) The P&A procedure for this well is shown in Attachment No. 11.

(14) Once the draft permit is issued, Petroglyph will conduct a Mechanical Integrity Test and a static bottom-hole pressure test. The MIT procedure is contained in Attachment No. 12. The conversion work will be satisfactorily completed and submitted to the EPA on Form 7520-12. A wellbore schematic will be included with this form.

- (15) Petroglyph will give proof of financial responsibility by posting a surety bond for the UIC well prior to final permit approval. A copy of this letter is contained in Attachment No. 13.
- (16) Petroglyph will install various gauges on the well so that the injection pressure and tubing/casing annulus pressure can be monitored. The well will be equipped with a flow meter with a cumulative volume recorder.

Ute Tribal 03-12 Injection

Well History:

Spud Well: 9/21/1996
 Completed: 10/21/1996
 First Production: 11/13/1996


Tops (KB)

BMSW* Found at 965'
 Green River 1490'
A Marker 4170'
 X Marker 4671'
 Douglas Creek 4818'
 B Limestone 5220'
 Castle Peak 5723'
Basal Carbonate 6150'

Injection Packer @ 4226'

Petroglyph Operating Co., Inc.
 Ute Tribal #03-12
 (2272' FSL & 575' FWL)
 NW SW Section 3, 5S- 3W
 Antelope Creek Field
 Duchesne Co. Utah
 API#: 43013317060000

*Plate 1 Utah Geological Survey Special Study 144. (2012). BMSW
 Elevation Contour Map, Uinta Basin, Utah. [map]. (CA 1:200,000)



GL: 5955'

KB: 5965'

8 5/8" 24# Surface CSG @ 251' KB
 cmt'd w/150 sx

Surface Hole size 12 1/4"

Hole Size 7 7/8" bit

Cement top @ 2290'
 5 1/2" 15.5# J-55 CSG @ 5963'
 cmt'd w/480 sx

Tubing 2 7/8" 6.5# J55

Perf's:

B05 4316' to 4330'
 B05 4347' to 4350'
 B07+ 4480' to 4492'
 B10 4566' to 4576'
 B11 4612' to 4615'
 B11 4615' to 4620'
 C08.1 5081' to 5084'
 C08.1 5084' to 5090'
 C08.1 5090' to 5095'
 D3 5380' to 5384'
 E01.1 5781' to 5782'
 E01.1 5782' to 5784'
 E01.1 5784' to 5789'
 E01.1 5789' to 5791'
 E01.1 5791' 5792'

PBTD @ 5914' KB

TD @ 6473' KB

(Not to Scale)

Ute Tribal 03-12 Well History

Well History:

Spud Well: 9/21/1996
 Completed: 10/21/1996
 First Production: 11/13/1996

Tops (KB):

BMSW* Found at 965'
 Green River 1490'
A Marker 4170'
 X Marker 4671'
 Douglas Creek 4818'
 B Limestone 5220'
 Castle Peak 5723'
Basal Carbonate 6150'

Perf History

10/15/1996


B10	4566' to 4576'
B11	4615' to 4620'
C08.1	5084' to 5090'
E01.1	5782' to 5784'
E01.1	5789' to 5791'

7/12/2011

B05	4316' to 4330'
B05	4347' to 4350'
B07+	4480' to 4492'
B10	4557' to 4566'
B10	4576' to 4578'
B11	4612' to 4615'
C08.1	5081' to 5084'
C08.1	5090' to 5095'
D3	5380' to 5384'
E01.1	5781' to 5782'
E01.1	5784' to 5789'
E01.1	5791' to 5792'

Petroglyph Operating Co., Inc.
 Ute Tribal #03-12
 (2272' FSL & 575' FWL)
 NW SW Section 3, 5S- 3W
 Antelope Creek Field
 Duchesne Co. Utah
 API#: 43013317060000

*Plate 1 Utah Geological Survey Special Study 144. (2012). BMSW
 Elevation Contour Map, Uinta Basin, Utah. [map]. (CA 1:200,000)



GL: 5955'

KB: 5965'

8 5/8" 24# Surface CSG @ 251' KB

cmt'd w/150 sx

Surface Hole size 12 1/4"

Cement top @ 2290'

5 1/2" 15.5# J-55 CSG @ 5963'

cmt'd w/480 sx

Hole Size 7 7/8" bit

Perf's:

B05 4316' to 4330'

B05 4347' to 4350'

B07+ 4480' to 4492'

B10 4566' to 4576'

B11 4612' to 4615'

B11 4615' to 4620'

C08.1 5081' to 5084'

C08.1 5084' to 5090'

C08.1 5090' to 5095'

D3 5380' to 5384'

E01.1 5781' to 5782'

E01.1 5782' to 5784'

E01.1 5784' to 5789'

E01.1 5789' to 5791'


E01.1 5791' 5792'

PBTD @ 5914' KB

TD @ 6473' KB

(Not to Scale)

Ute Tribal 03-12 Plug and Abandonment



Petroglyph Operating Co., Inc.

Ute Tribal #03-12

(2272' FSL & 575' FWL)

NW SW Section 3, 5S- 3W

Antelope Creek Field

Duchesne Co. Utah

API#: 43013317060000

*Plate 1 Utah Geological Survey Special Study 144. (2012).


BMSW Elevation Contour Map, Uinta Basin, Utah, [map]. (CA
1:200,000)

ATTACHMENT NO. 1: AREA MAP


1:12000

500 0 500 1000 ft


1 inch = 1000 feet














ATTACHMENT NO. 3:
Map of the "A" Lime Marker



1:30000



-  Producing Oil Well
-  Injection Well
-  Injection Well,
waiting on water
-  PTPI
-  D & A
-  Waiting on Completion
-  TA
-  Shut In
-  Injector Shut In
-  P & A
-  Shut In Gas Well



ANTELOPE CREEK
DUCHESNE COUNTY, UTAH

Structure Map of the "A" Lime Marker
(approximate top of Injection Zone)
in the Vicinity of the
Ute Tribal 03-12
With Line of Cross Section A to A'

hack 7-11-06

Revised by:
JG 10-3-14

Petroglyph Energy, Inc.: 555 S. Cole Rd., Boise, ID 83709

\\SERV\Geo\Utah Regional\CTI\03-12 structure map.gmp

Maximum Allowable Injection Pressure (MAIP)
From Fracture Gradient

Date: 09/04/2015 Operator: Petroglyph
Well: Ute Tribal 03-12
Permit #: _____

Enter the following values:

Specific Gravity of injectate =	<u>1.010</u>	g/cc
Depth to top of injection interval =	<u>4,170</u>	feet
Fracture Gradient (F G) =	<u>0.880</u>	psi/ft

MAIP = **1,845** psig

(rounded down to nearest 5 psig)

where:

$$MSIP = [FG - (0.433 * SG)] * \text{Depth to top of injection interval} = 1845.934$$

Cement Bond Index (in millivolts - mV)

Date: September 4, 2015

Operator: Petroglyph

Well: Ute Tribal 20-07

Permit :

Enter the following values:

Amplitude at 0% Bond (A-0) (in mV) = 72 mV

Amplitude at 100% Bond (A-100) (in mV) = 1 mV

Amplitude at 80% Bond (A-80) = 2.4 mV

$$[(0.2)\log A0 + (0.8)\log A100]$$

Amplitude at 90% Bond (A-90)= 1.5 mV

$$[(0.1)\log A0 + (0.9)\log A100]$$

Amplitude at 70% Bond (A-70)= 3.6 mV

$$[(0.3)\log A0 + (0.7)\log A100]$$

Amplitude at 60% Bond (A-60)= 5.5 mV

$$[(0.4)\log A0 + (0.6)\log A100]$$

Permit No: UT2

Well: UT 3-12

What Needs to be Done	Information Sources	Review & Evaluation Notes
Determine name, top and base of the confining zone(s) and the injection zone(s).	<input type="checkbox"/> Geologic data submitted <input type="checkbox"/> Well logs from area <input type="checkbox"/> Published articles	Conf Zone: top <u>3927</u> base <u>4170</u> Inj Zone: top <u>4170</u> base <u>6150</u> (Garden Gulch 2-Marker) (top Wasatch)
Determine name, top and base of all USDWs. List base of lowermost USDW: Determine which USDWs are actually being used for water supply.	<input type="checkbox"/> Geologic data submitted <input type="checkbox"/> nearby Water analyses <input type="checkbox"/> nearby Well logs <input type="checkbox"/> Water supply wells <input type="checkbox"/> Published articles	Surface Elevation: <u>61,5955</u> <u>K13 5965</u> Pub #92 base USDW: bgs: elev: submitted base USDW bgs: <u>965</u> elev: base of Uinta / top Green River: <u>1490</u>
Review and evaluate construction, casing and cementing records of proposed well.	<input type="checkbox"/> Data submitted <input type="checkbox"/> Completion/workover reports <input type="checkbox"/> Contractor invoices <input type="checkbox"/> Logs: CBL, RTS, Temp, casing inspection, etc.	TD: <u>6473</u> PBTD: <u>NOT DEFINED</u> surface csg <u>8 5/8" 24#</u> ft <u>0-251'</u> s: long strg csg <u>5 1/2" 15.5#</u> ft <u>0-5963</u> s: TOC: submitted: <u>2290</u> CBL: <u>2320</u> Wells in AOR: TD TOC C <u>03-05</u> <u>6472</u> <u>SURF</u> <u>04-09(TA)</u> <u>6630</u> <u>2370</u>
Review and evaluate construction, casing and cementing records of AOR wells that penetrate injection zone.	<p style="text-align: center;">72/1 2.4 = 280% OK</p>	
Review P&A plan for effective USDW protection, injection zone isolation and well closure.	<input type="checkbox"/> P&A plan <input type="checkbox"/> Area geology	plug depths:
Review amount of FR - is it adequate to cover P&A costs of proposed in P&A plan?	<input type="checkbox"/> contractor bids / P&A cost histories <input type="checkbox"/> nearby well P&A costs	FR instrument: Amount: \$
Calculate the maximum allowable injection pressure (MAIP).	<input type="checkbox"/> Fracture treatments <input type="checkbox"/> Step Rate Test results <input type="checkbox"/> Fracture gradient	top perforation: bottom perforation: injectate specific gravity: <u>1.01</u> Frac Gradient: <u>.88</u> p: initial MAIP = <u>1845</u> psi
Determine which logs and tests will be performed.		

Structural Cross Section A to A' in the Vicinity of Ute Tribal 03-12

43013515540000
PETROGLYPH OPERATING COMPANY
UTE TRIBAL 34-04-D3
660 FNL 762 FWL
TWP: 4 S - Range: 3 W - Sec. 34

8109 ft
PETROGLYPH OPERATING COMPANY INC
Ute Tribal 03-12
2272 FSL 575 FWL
TWP: 5 S - Range: 3 W - Sec. 3

1998 ft
PETROGLYPH OPERATING COMPANY
UTE TRIBAL 04-16
589 FSL 480 FEL
TWP: 5 S - Range: 3 W - Sec. 4

3035 ft
PETROGLYPH OPERATING COMPANY
UTE TRIBAL 09-07
2087 FNL 1910 FEL
TWP: 5 S - Range: 3 W - Sec. 9

3722 ft
PETROGLYPH OPERATING COMPANY
UTE TRIBAL 09-13
650 FSL 657 FWL
TWP: 5 S - Range: 3 W - Sec. 9

The diagram illustrates a structural cross-section through five wells. The vertical scale shows depth from -1000 to 2500 feet. Each well log displays GR, TVD, and ILD data. Correlation lines indicate stratigraphic continuity. Shaded regions highlight specific geological units. Total depths (TD) are provided for each well.